Supersedes:

None

5345A ELECTRONIC COUNTER SERIAL PREFIXES 1428 AND ABOVE INPUT AMPLIFIER FAILURES

If integrated circuit U1 or U2 (PN 1826-0151) fails on the 05345-60004 (A4) assembly, it must be replaced with a 1826-0290 integrated circuit. This IC is a special tested direct replacement for U1 and U2 in the 5345A. After replacement, the adjustments on A3 and A4 should be made as outlined in the Operating and Service manual. Also, be sure to update your parts list.

For 5345A counters below 1428, see Service Note 5345A-1.

DH/ka/WO 4–75/02



For more information, call your local HP Sales Office or East (201) 265-5000 ● Midwest (312) 677-0400 ● South (404) 436-6181 ● West (213) 877-1281. Or, write: Hewlett-Packard, 1501 Page Mill Road, Palo Alto, California 94304. In Europe, Post Office Box 85, CH-1217 Meyrin 2, Geneve, Switzerland. In Japan, Yokogawa-Hewlett-Packard, 1-59-1, Yoyogi, Shibuya-Ku, Tokyo, 151.

