

N8262A-03

Modification Recommended Service Note

Supersedes:
NONE

N8262A P-Series Modular Power Meter

Serial Numbers: MY50900121 to MY56040004, SG52420001 to SG55106001

Internal fan functionality and abnormal sound

Parts Required:

P/N	Description	Qty.
N8262-60104	Assy-Fan	1
3050-2249	Washer-Flat metallic 3.2mm-ID 6mm-OD 0.5mm-THK SST	3

ADMINISTRATIVE INFORMATION

ACTION	<input checked="" type="checkbox"/> ON SPECIFIED FAILURE	STANDARDS	
CATEGORY:	<input type="checkbox"/> AGREEABLE TIME	LABOR :	2 Hours (Average)
LOCATION	<input type="checkbox"/> CUSTOMER INSTALLABLE	SERVICE:	<input type="checkbox"/> RETURN USED <input type="checkbox"/> RETURN
CATEGORY:	<input type="checkbox"/> ON-SITE (active On-site contract required)	INVENTORY:	<input type="checkbox"/> SCRAP PARTS: <input checked="" type="checkbox"/> SCRAP
	<input checked="" type="checkbox"/> SERVICE CENTER		<input checked="" type="checkbox"/> SEE TEXT
	<input type="checkbox"/> CHANNEL PARTNERS		<input type="checkbox"/> SEE TEXT
AVAILABILITY:	PRODUCT'S SUPPORT LIFE	NO CHARGE AVAILABLE UNTIL:	30-November-2019.
	<input checked="" type="checkbox"/> Calibration Required	PRODUCT LINE:	[WN]
	<input type="checkbox"/> Calibration NOT Required	AUTHOR:	[LSL]


ADDITIONAL INFORMATION:

Situation:

We have received reports of some N8262A P-Series Modular Power Meters had a malfunctioning internal fan and/or abnormal sound due to the fan.

Solution/Action:

- For the fan functionality, open the chassis and turn on the power on the unit. Visually inspect the fan.
 - If the fan has malfunctioned, replace it with (N8262-60104) Assy- fan.
- For abnormal sound originating from the fan.
 - If the noise was due to the fan blade rubbing against fan guard, added a washer (3050-2249) in between the fan and fan guard on each location to raise up the fan guard. This will prevent the fan blade from rubbing against fan guard.



Revision History:

Date	Service Note Revision	Author	Reason for Change
12 FEB 2017	01	LSL	As Published